

THIS DETAIL IS GUIDE ONLY - EACH INDIVIDUAL
AREAWAY WILL REQUIRE SPECIAL DESIGN

DUR-O-WALL TRUSS
REINFORCEMENT OR
EQUIVALENT TO BE
USED AS HORIZONTAL
REINFORCEMENT IN
CONCRETE MASONRY
WALL UNIT

IF REQUIRED, REMOVE
AREAWAY WALL TO
AREAWAY FLOOR AT
BUILDING LINE TO
PERMIT CONSTRUCTION
OF NEW WALL

EXISTING CONCRETE FLOOR SLABS IN
AREAWAYS TO BE BROKEN INTO PIECES
HAVING AN AREA OF NO MORE THAN
2 SQUARE FEET

REMOVE AND DISPOSE OF MISCELLANEOUS
DEBRIS FROM AREAWAY

BACKFILL WITH SELECT STRUCTURE FILL

EXISTING CELLAR WALLS TO BE
DEMOLISHED TO A DEPTH OF
4'-0" BELOW FINISHED GRADE
(UNLESS OTHERWISE NOTED)

CEMENT PARGING 2
COATS, $\frac{1}{2}$ " THICK,
AND BITUMINOUS
ASPHALT 2 COATS
(NEW CONCRETE
MASONRY AND
EXISTING BUILDING
WALL EXPOSED)

NEW 12" CONCRETE
BLOCK MASONRY
UNITS

A ←

A ←

EXISTING BUILDING
FOUNDATION WALL

EXISTING LINTEL

12" MINIMUM

PLAN

SEE SECTION A-A DETAIL R592-2

NOTES:

1. EXISTING ROOF SLAB/SIDEWALK SYSTEM TO BE
DEMOLISHED AND MATERIALS REMOVED FROM AREAWAY.
2. PARGE AND WATERPROOF NEW AND OLD WALLS
EXPOSED TO BACKFILL

CITY OF ROCHESTER

AREAWAY ABANDONMENT OUTSIDE

ISSUED

9-2-91

STD. DWG.

REVISED

2-15-00

NO. R592-1