

ATTACHMENT E

Soils and Section Cut and Fill Report 8/1/11

Section Cut & Fill Report

JOB: 2722 Brooks Landing SECTION: 19 conceptual plan cn130 5_4

Grid Size: 3.00 X 3.00 Ft Subgrid Size: 1.50 X 1.50

Section Size: 349.2 X 403.3 Ft

Area of Cut: 22340 SqFt Area of Fill: 23090 SqFt Total Work Area: 46015 SqFt

(Cut Area Threshold: 0.01Ft Fill Area Threshold: 0.01Ft)

Section Balance Analysis

	Bank (CY)	Compacted (CY)	Expanded (CY)
Fill Required		2989	
Repl Topsoil Rqd		0	
Stripping Total	0	0	0
Cut Total	880	880	880
Fill Obtained On Site	880	880	880
Repl Topsoil Obtained On Site	0	0	0
Import Repl Topsoil		0	
Import Fill		2109	
Export Stripping		0	0
Export Fill		0	0
Total Export		0	0

Shrinkage and Expansion

Shrinkage (%)	0
Expansion (%)	0
Repl Topsoil Shrink (%)	0