

Water Supply Conduit Modernization, Phase 2: South Clinton Avenue, Conduit 2 and 3 Brighton-Henrietta Town Line Road to I-590



Public Information Meeting March 25, 2013

AGENDA



- Welcome and Introductions
- Conduit Description and History
- Project History
- Project Limits
- Proposed Alignment
- Construction Impacts
- Project Schedule and Cost
- Questions and Comments

Project Contacts

Rochester Water Bureau

- Robert Morrison Director
- Enrique Maisch
- Pat O'Connor

Bergmann Associates

- Julie Barnes
- Jim Raleigh
- Tom Detrie

Villager Construction

- Ed Nelson
- Jim Lehr

Project Manager Engineer in Charge Project Engineer

Managing Engineer

Project Manager

Project Manager Superintendent



Rergmann architects // engineers // planners





Conduit Description



architects // engineers // planners

- Water comes from Hemlock and Canadice Lakes (28 miles south of Rochester)
- Water is treated and sent to Rush Reservoir
- From Rush Reservoir, sent north via 3 large diameter conduits to Highland and Cobbs Hill Reservoirs



Conduit History

Conduit 1

- 24" Cast Iron 1875
- Follows East Henrietta Road

Conduit 2

• 38" Riveted Steel - 1894

Conduit 3

- 37" Lockbar Steel 1916
- Conduits 2 and 3 follow East Henrietta Road / South Clinton Avenue





Project History



2007 - Water Supply Planning Study

 Highest priority location due to location, condition, and history of breaks

2008 - 2010 - Phase 1

- Installed single 42" steel water main
- I-590 to Suburban Court

Fall 2011 – Phase 2 Design Begins

• Brighton-Henrietta Town Line Rd to I-590

March 2013 – Begin Phase 2 Construction

- Single 42" cement mortar lined steel water main
- Cured-In-Place-Pipe (Rehabilitation)





Reasons for the Project

Planning Study Summary

- Recent and severe breaks, as recent as (2004)
 - 2002 Leak on Conduit 3 at Woodsmeadow Lane
- High operating pressures
- Over 100 years old








www.bergmannpc.com

architects // engineers // plan





South Clinton Avenue Brighton-Henrietta Town Line Rd to I-590



Proposed Alignment



Brighton-Henrietta Town Line Rd to Woodsmeadow Ln



Proposed Alignment



Woodsmeadow Ln to Erie Canal








Erie Canal to I-590



Proposed Alignment



Under Erie Canal




Under I-590



Proposed Alignment



Cured-in Place Pipe



Traffic Control

- Includes:
 - Lane / shoulder closures
 - One-way detour
 - Night / weekend work
- Normal working hours will be 7:00 am to ~ 5:00 pm
- 1 2 day driveway interruptions (east side)
- Sidewalks will be open during construction








Bergmann architects // engineers // planners

Traffic Control Overview



Section Between BHTL Rd to Woodsmeadow Ln



Berg

architects // engineers // planners



Northbound Detour Route



v.bergmannpc.com

One-way Detour

- Southbound Traffic Maintained
- Northbound Traffic Detoured
- BHTL Rd to Woodsmeadow Lane
- Limited to a two (2) month duration
- Begins June 2013
 - Handouts / Public Notice
 - Variable Message Boards





Night / Weekend Work

- Weekend/night work will occur at the Brighton-Henrietta Town Line Rd Intersection
 - Intersection will be controlled by flag person(s)
 - Lane closures on BHTL Rd and South Clinton Ave
 - Begin Friday 8:00 pm complete Monday 6:00 am or 8:00 pm to 6 am following day
- Night work will occur between Erie Canal (south side) and I-590 (north side)
 - If required for rehabilitation work
 - Potential lane closures on South Clinton Ave







Bergmann architects // engineers // planners

Night Work Locations



Construction Impacts



.com

BHTL Rd Intersection – Weekend Work



Anticipated Impacts



- Minor water service or other utility interruptions
 - Will be coordinated in advance
- Restoration:
 - Milling and resurfacing
 - **o** BHTL Rd to just north of Woodsmeadow Lane
 - Minor changes to the traffic control patterns as requested by MCDOT
 - Topsoil and lawn restoration
- Trench Safety:
 - Open trenches will be protected with fence daily



Project Schedule and Cost

Proposed Schedule

Begin Pipe Placement:

One-Way Detour:

<u>Cost</u>

Various Tie-in / Linings:

Conduit Abandonment:

Milling and Resurfacing:

May 2013 June/July 2013 Fall 2013 Winter 2013 Spring 2014

Est. Cost (Design/Construction): \$7.0 Million





Contact Information



- Project Field Office
 - 1815 South Clinton Ave, Suite 320 (585) 730-7827
- Full time onsite inspection team
 - Jim Raleigh Bergmann Associates (716) 652-4098
- Updates to be posted on the City of Rochester website – <u>www.cityofrochester.gov/southclinton</u>
- Contact:
 - Ed Nelson Villager Construction, Inc. (585) 370-0448
 - City of Rochester Water Bureau Helpline (585) 428-7500



Water Supply Conduit Modernization, Phase 2: South Clinton Avenue, Conduit 2 and 3 Brighton-Henrietta Town Line Road to I-590



Public Information Meeting March 25, 2013