#### **AGENDA**

## BRECK STREET IMPROVEMENT PROJECT PUBLIC INFORMATIONAL MEETING

# BRECK STREET (PALMER STREET TO HERKIMER STREET) PALMER STREET (BRECK STREET TO EAST MAIN STREET)

**DATE:** December 19, 2019 **TIME:** 6:30 P.M.

**LOCATION:** RTS - Administration Building (1372 East Main Street)

#### I. Introduction

City of Rochester, Department of Environmental Services:
Dominic Fekete, Managing Engineer/Street Design Division
Lisa Reyes, Engineer III/Street Design Division
Javier Vargas, Engineer II/Street Design Division

#### II. General Project Description

- o Breck Street widening by 2 feet from 22 feet to 24 feet
- o Palmer Street will not be widened to remain 24 feet wide
- New granite curbing with underdrain system
- New driveway aprons to legal driveways; driveway apron removals to illegal driveways and vacant parcels (illegal driveway letters sent to owners – see below)
- Removal of carriage walks to properties with driveways; replacement/installation of carriage walks to properties without driveways
- o Drainage improvements to include new catch basin installations
- Some relocations of existing light poles impacted by the Breck Street widening
- Hazardous and asphalt covered sidewalk replacements
- Three (3) tree removals (39, 92 and 155 Breck St); 2 are due to poor condition and will be removed ahead of the project by City Forestry (92 & 155 Breck St); replacement trees to be installed
- o Restoration of all disturbed areas affected by the construction
- Existing alternate side parking regulations will remain

## III. <u>Illegal Driveway & Encroachment Letters:</u>

- Illegal Driveway Letters: owners of the following Breck St. properties were sent driveway letters dated December 6, 2019: 10-16, 32, 94-96, 117-123, 135, 154-156, 155, 158-160, 208, 213, 224, 249, 274, and 278.
- Encroachment Letters: letters will be mailed out soon to property owners who have private items within the right of way (i.e. retaining walls, fences, shrubs/bushes, flowers, planters, paver stones, etc.).

#### IV. Utility Work

- Water Bureau lead water service replacements to be completed prior to the street construction project.
- o RGE (Electric) some underground electric ducts will require replacement.
- RGE (Gas) test pits will be performed to determine depth of services; some services may need to be lowered below the curb and underdrain.
- o Frontier concerns with relocating the existing utility pole at 288 Breck St out of the proposed driveway apron. Further coordination is required to determine a solution.
- Spectrum/Charter similar concern as Frontier regarding utility pole at 288 Breck St.
  Test pits will be performed to determine depth of their conduits; conduit may need to be lowered below the curb and underdrain.

#### V. Maintenance of Traffic

- o Two-way traffic will be maintained using flag persons when necessary.
- Some access disruptions during curb, sidewalk and driveway placement.

#### VI. Schedule

Advertise
 Begin Construction
 Complete Construction
 Fall, 2020

#### VII. Questions and Comments

### VIII. Contacts

Javier Vargas, DES/Street Design Division – Design Phase City of Rochester 585-428-7164 javier.vargas@cityofrochester.gov

Lisa Reyes, DES/Street Design Division – Design Phase City of Rochester 585-428-6354 lisa.reyes@cityofrochester.gov

Jim Quackenbush, DES/Permits Division – Design Phase City of Rochester 585-428-6791

james.quackenbush@cityofrochester.gov

Matthew Simonis, NBD/Zoning Division – Design Phase City of Rochester 585-428-6637 matthew.simonis@cityofrochester.gov

Andrew Wojewodzic, DES/Construction Division – Construction Phase City of Rochester 585-428-6523 <a href="mailto:andrew.wojewodzic@cityofrochester.gov">andrew.wojewodzic@cityofrochester.gov</a>