

SECTION S209 – SOIL EROSION AND SEDIMENT CONTROL

S209 GENERAL

Work is to be in accordance with requirements of NYSDOT Section 209 Soil Erosion and Sediment Control, with following modifications:

References to NYSDOT specifications are to be in accordance with latest edition of *NYSDOT Standard Specifications (US Customary Units)*.

S209-4 METHOD OF MEASUREMENT

Under NYSDOT Section 209-4 Method of Measurement, **DELETE** Subsections 209-4.01 Temporary Mulch, 209-4.02 Temporary Seed and Mulch, 209-4.04 Temporary Strawbale, 209-4.05 Temporary Silt Fence, 209-4.09 Drainage Structure Inlet Protection and 209-4.11 Construction Entrances in their entirety and **REPLACE** with following:

S209-4.01 Temporary Seed or Mulch

Quantity to be measured for payment will be number of square feet of area temporarily mulched or seeded, to nearest square foot.

S209-4.02 Temporary Seed and Mulch

Quantity to be measured for payment will be number of square feet of area temporarily seeded and mulched, to nearest square foot.

S209-4.04 Temporary Straw Bale

Quantity to be measured for payment will be number of linear feet of straw bale dike constructed as measured along face of dike, to nearest foot.

S209-4.05 Temporary Silt Fence

Quantity to be measured for payment will be number of linear feet of silt fence dike constructed as measured along face of dike, to nearest foot. No measurement will be made for seams or overlaps.

S209-4.09 Drainage Structure Inlet Protection

Quantity to be measured for payment will be number of drainage structure inlet protected, regardless of height of gravel bag dike.

S209-4.11 Construction Entrances

Quantity to be measured for payment will be number of square feet of construction entrances constructed, to nearest square foot. No measurement will be made construction entrances associated with Contractor's operations.

S209-5 BASIS OF PAYMENT

Payment will be made under:

ITEM NO.	ITEM	PAY UNIT
S209.30	Mulch - Temporary	Square Feet
S209.31	Seed - Temporary	Square Feet

ITEM NO.	ITEM	PAY UNIT
S209.32	Seed and Mulch - Temporary	Square Feet
S209.22	Straw Bale - Temporary	Linear Feet
S209.34	Silt Fence - Temporary	Linear Feet
S209.35	Drainage Structure Inlet Protection, Silt Fence - Temporary	Each
S209.36	Drainage Structure Inlet Protection, Gravel Bag - Temporary	Each
S209.37	Drainage Structure Inlet Protection, Prefabricated - Temporary	Each
S209.38	Drainage Structure Inlet Protection, Concrete Block - Temporary	Each
S209.39	Construction Entrance	Square Feet

REVISED December 1, 2015