




PAVEMENT SECTION	X" BASE COURSE	A (Ø PIPE)	B (BOTTOM TRENCH)
LIGHT-DUTY	0"	2' - 6"	3' - 2"
MEDIUM-DUTY	3"	2' - 9"	3' - 5"
MODIFIED	6"	2' - 11"	3' - 7"
HEAVY-DUTY	8"	3' - 1"	3' - 9"

NOTES:

1. WIDTH OF CURB IS TO BE AS REQUIRED IN CONTRACT DOCUMENTS.
2. SIDEWALK ACCESS RAMP HEADER CURB IS TO BE FLUSH WITH PAVEMENT SURFACE.
3. DRIVEWAY HEADER CURB IS TO HAVE CURB REVEAL OF 1 1/2 INCHES.
4. ONLY TRANSITION AND HEADER CURB PIECES USED FOR DRIVEWAYS ARE TO BE ROUNDED.
5. TACK COAT TO BE APPLIED BETWEEN ALL LIFTS OF HMA COURSES.
6. PAVEMENT SEAMS TO BE SEALED WITH BITUMINOUS SEALER IN ACCORDANCE WITH NYSDOT MATERIAL DESIGNATION 702-0700.

CITY OF ROCHESTER

STONE CURB REPLACEMENT - ASPHALT BASE

ISSUED	12-30-11	NON-STANDARD DWG.NO.S609-16
REVISED	12-1-15	